


10836 County Rd 2
P.O. Box 70
Grafton ON, K0K 2G0
www.ahtwp.ca



Telephone: 905-349-2700
Fax: 905.349.3259
bmcmillan@ahtwp.ca

Brian McMillan, CRS-S
Manager of Public Works / Parks & Recreation

Council Report

Council Date: May 19th, 2022

To: Mayor Latchford and Members of Council

Prepared By: Brian McMillan, CRS-S
Manager of Public Works / Parks & Recreation

Reviewed By: Troy Gilmour, CAO

Approved By: Troy Gilmour, CAO

Subject: List of 2022 Construction Projects

Recommendation:

"Be it resolved that Council of the Township of Alnwick/Haldimand receive and file the Manager of Public Works / Parks & Recreation's List of 2022 Construction Projects."

Background:

Below is a list of our 2022 Construction Projects with a brief description of the scope of work:

Full Reconstruction – brushing, tree removal, ditching, culvert replacement, pulverizing road and shaping, gravel application and shaping, and 2 layers of surface treatment.

ROAD	DESCRIPTION	DISTANCE
VERONVILLE RD	From Rutherford Rd to County Rd 2	1.6 km
CURTIS POINT RD	From County Rd 18 to Rice Lake	2.3 km
MCDONALD RD	From County Rd 22 to Bridge	0.2 km

Reconstruction – brushing, tree removal, ditching, culvert replacement, gravel application and shaping, and 2 layers of surface treatment. This section of road is going from a gravel surface to a surface treated rd. Boundary Rd with Trent Hills so expenditures is 50/50. Majority of worked completed by Trent Hills.

ROAD	DESCRIPTION	DISTANCE
BAXTER RD	From Webb Rd to Sandy Bay Rd	2.2 km

Resurfacing – some shoulders may need to be taken off to make sure water runs off road and into ditches. Roads will be patched extremely well prior to a single layer of surface treatment being applied.

ROAD	DESCRIPTION	DISTANCE
DAVIDSON RD	Entire Road	1.0 km
MACKLIN RD	Entire Road	1.8 km
GRILLS RD	Entire Road	2.3 km
HOSKIN RD	Entire Road	2.1 km
ORCHARD GROVE RD	Entire Road	3.8 km
MCDONALD RD	Entire Road	1.8 km
SPEECHLEY RD	Entire Road	1.1 km
STEWART RD	Entire Road	3.0 km
BENLOCK RD	Entire Road	1.5 km
BARNBUM HOUSE RD	Entire Road	0.5 km

Rehabilitation – road is currently surface treated but is in rough shape will be pulverized and shaped and have calcium put down for this year and then surface treated in 2023. Portion of road from County Rd 9 past Donkey Farm will be left surface treated.

ROAD	DESCRIPTION	DISTANCE
BOWMANTON RD	From County Rd 9 to Beagle Club Rd	1.4 km

Fall projects:

- 0.4 km of 3rd line in Roseneath from County Rd 45 to gravel section & 0.4 km of Division St between County Rd 45 and 3rd line will have brushing, tree removal, ditching & culvert replacement done in preparation to have these two urban sections paved in 2023.
- 0.3 km of Boyle Rd from County Rd 23 to top of hill will be dugout, “B” gravel added, geotextile cloth put in, and “A” gravel added. The plan would then be to have 2 layers of surface treatment put down on this road section in 2023. This section of road now has been fully developed with new homes and is gravel currently but there are clearly base issues in the road and this road is in really in rough shape during the spring.

Consultations:

Discussion with Public Works Staff.

Actions:

No actions required.

Legislative Authority/Risk Considerations:

None

Financial Impact:

These projects will be completed within the approved 2022 Capital & Operational Budget.

Conclusion/Outcomes:

If there are any questions regarding this report, I will gladly respond to them.

Attachments:

None attached.

Respectfully submitted,

Brian McMillan, CRS-S
Manager of Public Works / Parks & Recreation



Approved by CAO
Troy Gilmour, C. Tech., rcji

May 12/2022
Date